


# THE EVOLUTION TOWARDS CONTEMPORARY CLIMATE RESPONSIVE DESIGN: Part One



Drawing by LeCorbusier

The Positive Potential of Learning From Bio-Climatic Practices


## High Level Ideas:

- Did people do better with respect to **climate responsive design**
  - *Before* the interference of architects and engineers?
  - *Before* the invention of HVAC
- Was **colonialization** responsible for the eradication of successful **indigenous** building practices?
- Is **Globalization** currently responsible for taking the evolution of bad colonial practices that culminated in International Style architecture to even more places (that are climatically inappropriate)



## The Origins of Modern Town Planning

Leonardo Benevolo



## Origins of our current climate problem

- Most of the development of North America was based on well intentioned European thinking
- Industrialized cities were generally not respectful of anything nature or climate based – there was a focus on formal layouts, organized streets, architectural styles
- Rivers were simultaneously a source of water for drinking (life), water to feed industrial processes, and the place to dump sewage
- Hard to believe but people didn't understand the basics that when you dump feces into the river, and drink that water, you might get cholera and die

Technological advances have allowed us to build anything without concern for how it should be economically/environmentally heated and cooled.



Photo: National Trust

The Glass House New Canaan Connecticut 1949, by architect Phillip Johnson who coined the term “International Style”



# Conventional construction:

*Boxes hooked up to life support*



In Florida turn the dial one way,  
in Waterloo turn it the other.



Think Building Green.com



CONNECTICUT



ARIZONA

04.20.2012



NEW MEXICO



FLORIDA

BCAR 2010





Chicago



# GLOBALIZATION

Shanghai



Dubai





COLD

Chicago



HOT

GLOBALIZATION

Shanghai




HOTTER



Dubai



Paris, Texas, Canada, Jamaica?? Can you tell which is which??



# Climate Responsive Architecture



Pompeii: House of the Vettii



Tangier: inside a Medina House

“We must begin by taking note of the countries and climates in which homes are to be built if our designs for them are to be correct. One type of house seems appropriate for Egypt, another for Spain...one still different for Rome...It is obvious that design for homes ought to conform to diversities of climate.”

*Vitruvius, Architect 1<sup>st</sup> century BCE*



# Primitive Architecture and Climate

1960

*Despite meager resources, primitive people have designed dwellings that successfully meet the severest climate problems. These simple shelters often outperform the structures of present-day architects*

by James Marston Fitch and Daniel P. Branch

This is the required reading that accompanies today's lecture.

# SILENT SPRING



*The* CLASSIC *that* LAUNCHED  
*the* ENVIRONMENTAL MOVEMENT

# RACHEL CARSON

*Introduction by* LINDA LEAR *Afterword by* EDWARD O. WILSON

**1962**

This book launched environmental consciousness in the 20<sup>th</sup> century.


Rachel Carson connected the negative health impact of DDT (pesticide) on human health.

Surprisingly before that time people didn't appreciate that you sprayed it on plants, it rained, the rainwater entered the ground, ended up in ponds, cattle drank the water, and people ingested DDT.



**1963**

Victor Olgay establishes the relationship between original indigenous practices, building form, climate (based on Fitch and Branch) and *human comfort*.



**2015**

The second environmental movement demanded a reprint to the out of print original text.

Olgay's basic ideas about climate and its relationship to **HUMAN COMFORT** were to become the basis for thinking in current sustainable design.






Victor Olgay, 1963, introduced the concept of the **COMFORT ZONE**.

There is little point of saving energy if the building is not comfortable for the occupants.

You can have reasonable comfort without heating or AC.



46. Schematic bioclimatic index.




## Farnsworth House, 1945-51



Occupant thermal comfort was never a priority in highly formal projects like these. Mies didn't even want the owner to install drapery! The windows are all sealed. No natural ventilation. No built in shading. The majority of modern buildings were constructed sealed.





**1979**

The 1970s saw a surge in interest in the design of solar responsive buildings. Edward Mazria's book became the basis of work in this area.

**2009**

Mazria founded architecture2030 and challenged all architects to design to zero carbon operating energy by the year 2030.



<https://architecture2030.org/>

The image shows the front cover of the book 'Design with Nature' by Ian L. McHarg. The cover is circular and features a dark, atmospheric photograph of a city skyline at dusk or dawn, with the buildings silhouetted against a lighter sky. The title 'DESIGN WITH NATURE' is printed in a bold, sans-serif font, with 'DESIGN' on the top line and 'WITH NATURE' on the line below. The author's name, 'IAN L. McHARG', is centered below the title in a smaller, all-caps sans-serif font.

DESIGN  
WITH NATURE

IAN L. McHARG

**1969**

Ian McHarg looks at the relationship of landforms to planning decisions.

Works against the modern notion of eradicating the landscape.

**1995**

The out of print book is resurrected as its ideas become the basis of current sustainable practices in development ideas.

Reyner  
Banham

Second  
Edition

The  
Architecture  
of the  
Well-tempered  
Environment



**1984**

This important text looked at the failure of Modern Architecture as it became reliant on mechanical heating and cooling systems.

The abandonment of good building practices that had environmental benefits.

Reyner Banham was a highly respected writer and so had a lot of influence.





# Architecture Without Architects

A Short Introduction  
to Non-Pedigreed  
Architecture

**Bernard Rudofsky**

**1987**

This seminal text looked at historic architecture from around the world.

It didn't have an environmental focus, necessarily, but was looking at building practices that were less formally driven.

Buildings that relied on local materials, ideas and skills.

"Provocative, and could well provide one viable answer to the wake-up call that Rachel Carson sounded . . . in *Silent Spring*."

—SAN FRANCISCO CHRONICLE

# BIOMIMICRY



Innovation Inspired  
by Nature

JANINE M. BENYUS

Now a two-hour public television special on  
*The Nature of Things* with David Suzuki

**1997**

Janine Benyus introduces the concept of Biomimicry.

The larger idea is that nature has already solved so many problems that people/technology struggles to solve.

If we closely examine how nature does things, we can figure out how to adapt these functions to our own fabricated objects.




# Remaking the Way We Make Things

2002

William McDonough and Michael Braungart put forward the idea that instead of objects being inevitably trashed, that we can change the way we make things to make use of waste to make new objects. All materials have value and all are limited in availability.


# cradle to cradle

William McDonough & Michael Braungart



# Climate Agreements

## A brief history



Many efforts have been made to get the countries of the world working to slow down climate change




None have been very effective

Much of the disagreement lies in disparity in population density, poor vs rich countries, developed vs developing countries

Developing countries do not think it fair to thwart their "progress" towards having lifestyles equal to developed countries.



# Global emissions since Kyoto



## The key issues at Copenhagen

- 1 Cut carbon in rich world**  
Scientists say cuts of 25-40% by 2020 are needed, relative to 1990 levels. Rising to 80-95% by 2050. Developed countries have grown rich on fossil fuels and still emit vast amounts of CO2 per person, so have a responsibility to make deepest cuts.
- 2 Curb carbon in developing world**  
Emissions from fast-growing economies such as China and India are surging, yet their citizens have small carbon footprints and millions live in poverty. So they'll argue they need to be allowed to pollute for a while yet as they improve their citizens' lives.
- 3 Pay the price for climate change**  
All agree that the poorest nations need urgent aid, having done nothing to pollute the atmosphere. It will also cost a lot to create the clean technology essential for slashing global emissions. In both cases, rich nations will be expected to pick up the tab.
- 4 Keep tabs on funds and emissions**  
Poorer nations want to continue Kyoto's top-down approach, with clear responsibilities placed on rich countries. Developing nations also want climate funds distributed by the UN, whereas developed countries would prefer the World Bank.
- 5 Slow the speed of deforestation**  
About 17% of the carbon emitted by human activity comes from razing forests. But paying people not to fell trees soon becomes complex... Who really owns them? Were they actually to be chopped down? How do you verify the whole process?
- 6 Clean technology**  
Paying for clean technology is just the start, as the products and services required must be developed and deployed rapidly and efficiently all over the globe. But nations differ on whether a strong international body is needed, or just an advisory one.

### Checklist of success

- Rich nations commit to a combined reduction in greenhouse gases of 25-40% by 2020.  
Chance of success: **Middling**
- Developing nations commit to a 15-30% cut on the emissions levels expected in 2020.  
Chance of success: **Good**
- Richer nations commit to funding poorer ones, and clean technology, to tune of \$200bn per year.  
Chance of success: **Low**
- Deal done on who monitors countries' carbon emissions and distributes the money.  
Chance of success: **Low**
- Agreement which delivers cash to forested nations, meaning far fewer trees are cut down.  
Chance of success: **Good**
- Deal that delivers a radical overhaul in the deployment of clean technology.  
Chance of success: **Fair**

## Total carbon emissions, 1997-2007

Rank	Country	Million tonnes	Percent change	Rank	Country	Million tonnes	Percent change
1	United States	64,958	7				
2	China	14,300	103				
3	Europe	50,370	5				
4	Japan	13,342	9				
5	India	11,870	60				
6	Germany	9,487	6				
7	Canada	6,385	8				
8	United Kingdom	6,281	1				
9	South Africa	4,504	29				
10	Italy	4,997	9				
11	Saudi Arabia	3,663	59				
12	France	4,466	5				
13	Spain	3,740	9				
14	Australia	4,203	9				
15	Russia	17,360	15				
16	Iran	4,128	59				
17	South Korea	5,059	9				
18	Ukraine	3,722	15				
19	Sweden	648	4				
20	Poland	3,308	6				
21	Indonesia	3,049	64				
22	Taiwan	2,909	9				
23	Netherlands	2,850	1				
24	Turkey	2,313	6				
25	Thailand	2,194	60				
26	Kazakhstan	1,790	102				
27	Belgium	1,619	6				
28	Venezuela	1,589	26				
29	Argentina	1,544	26				
30	Egypt	1,497	25				
31	Malaysia	1,454	64				
32	UAE	1,429	59				
33	Singapore	1,397	64				
34	Pakistan	1,240	59				
35	Uzbekistan	1,237	102				
36	Greece	1,124	6				
37	Romania	1,112	6				
38	Czech Rep.	1,045	6				
39	Nigeria	1,028	25				
40	Algeria	941	25				
41	Austria	781	6				
42	Switzerland	644	6				
43	Hungary	641	6				
44	Slovakia & Macedonia	519	6				
45	Slovenia	518	6				
46	Bulgaria	559	6				
47	Israel	701	59				
48	Portugal	678	6				
49	Denmark	644	6				
50	Finland	606	6				
51	Denmark	644	6				
52	Belarus	649	6				
53	Latvia	641	6				
54	Lithuania	641	6				
55	Poland	3,308	6				
56	Poland	3,308	6				
57	Poland	3,308	6				
58	Poland	3,308	6				
59	Poland	3,308	6				
60	Poland	3,308	6				

## The summit in numbers

- 15,000**  
Number of delegates expected to attend official Copenhagen summit
- 40,500**  
Tonnes of carbon dioxide predicted to be emitted by those delegates while at the summit
- 700,000**  
Cost in euros of replacing outdated boats in Bangladesh, paid for by Danish government to offset those emissions
- \$62m+**  
Estimated cost to Danish government of staging the event
- 65%**  
Minimum proportion of food and drink provided to delegates that will be organic

The data is the latest available compiled by the Environmental Information Administration, part of the US Department of Energy. Although we have made every effort to make the data as accurate as possible, we are not liable for any errors or omissions. The data is the best available source of carbon emissions for every country in the world.

SOURCE: WORLD RESOURCES INSTITUTE 2000-07 (WORLD STEEL REPORT)

Buildings and the layout of our urban environments are responsible for climate change.

Engineers and architects are the professionals that must learn and apply better ways of designing buildings to reduce their greenhouse gas emissions

This means reducing their operating energy requirements and dependence on fossil fuels

**Ecological justice:** it is the poor and marginalized that are the worst impacted by climate change. Desertification, floods, extreme weather events.




## The Global Warming Pie


These values look at Secondary Energy Use by Sector in Canada (2006)  
(energy used by the final consumer i.e. operating energy)

# Emissions and their Sources


U.S. GHG Emissions Flow Chart









1980




1985




1993



1983



1991



2006



SOCIETY OF  
BUILDING SCIENCE  
EDUCATORS

All of these authors are colleagues. They work at different universities. I am friends with all of them through my work with SBSE.



# Why do we build buildings, NOW???

Initially, it was for shelter from the outside weather, and thus, survival.



THEN, people desired a certain minimum level of COMFORT, but would modify clothing or expectations as a function of the weather.


NOW, people (due to the invention of HVAC) expect to be held at a constant level of COMFORT, in spite of the weather or location (in the world).

# Climate and Housing

In its most fundamental form, housing is shelter – a system of components designed to mediate the existing environments (which is less than satisfactory in some way) into a comfortable and satisfactory environment. Historically, shelter has been built

- to reduce the range of local climatic variations;
- to avoid some of the heat of the sun in hot climates,
- to conserve heat in cold climates,
- to welcome the breezes when they can provide desired cooling,
- to avoid winds when they serve to compound the problems of an already cold environments,
- to admit light in sufficient amounts for task lighting and to keep out excessive or unnecessary light.

# Shelter and Environment



35. Theoretical approach to balanced shelter.

DWC




- Shelter is the main instrument for fulfilling the requirements of comfort. It modifies the natural environment to approach optimum conditions of livability.

- The architect and engineer's problem is to produce an environment that will not place undue stress upon the body's heat-compensation mechanism

- *It is NOW our task to make utmost use of **the natural means** available in order to produce a more healthful and livable building, and to achieve a saving in cost by keeping to a minimum the use of mechanical aids for climate control – thereby reducing demand for fossil fuels and lowering CO2 levels*

# The Effects of Climate on People



36. Relation of human body to the climatic elements.

Major elements of climatic environment which affect human comfort are:


- Air temperature
- Radiation
- Air movement (Wind Speed)
- Humidity

“Thermal Comfort – that condition of mind which expresses satisfaction with the thermal environment.”

*ASHRAE Standard 55-66*



# Bodily Heat Transfer



16 37. Heat exchange between man and surroundings.

## Heat Gains:

- Metabolism (conversion of food to activity and heat)
- Absorption of Radiant Energy
- Heat Conduction Toward Body

## Heat Loss Through:

- Evaporation
- Conduction
- Convection (Wind Chill Factor)
- Radiation




Figure 2.1: Maintaining the thermal balance by equalizing heat gain (due primarily to metabolic heat generation) and heat losses (by convection, radiation, conduction, and evaporation).

# The Comfort Zone

The Comfort Zone refers to the **range of temperature conditions** of air movement, humidity and exposure to direct sunlight, under which a moderately clothed human feels “comfortable”.

This will be different for **Indoor** versus **Outdoor** conditions.

*This will be different for different cultures and climate conditions - what are people used to??*

We need our buildings to not only create comfortable indoor environments, but also pleasing and useful spaces outside of our buildings.







In a hot climate,  
where do people  
choose to sit?


Conversely when it is  
cold, people sit in  
the sun.



# The Comfort Zone


The comfort zone is the kidney shaped area that defines the range of conditions within which North Americans express no *great* objection.

However, the intersecting red lines show the temp and RH that we strive have been accustomed to striving for in our *interior* environments, winter, summer, Arctic, Florida!



45. Bioclimatic Chart, for U.S. moderate zone inhabitants.






46. Schematic bioclimatic index.

This adaptation is from "Design with Climate" by Victor Olgay, first published in 1963.

One of the biggest adjustments that must be made in trying to design buildings with less dependency on mechanical heating and cooling, is the adaptation of human expectations to have their environments held at a constant Temperature and Relative Humidity.



23C 35%RH



*All indoor temp and RH that falls outside of 23C 35%RH normally has called for mechanical and electrical intervention!!*





*i.e. \$\$\$ and fuel and CO2 emissions*



A close-up photograph of a tree branch heavily laden with snow and ice. The branch is the central focus, with intricate ice formations and snow clumps. The background is a blurred winter scene with more snow-covered branches and a bright, overcast sky. A black rectangular text box is overlaid in the center of the image.

Climate as the **Starting Point**  
for a  
Climate Responsive Design






There are many different ways to create graphic north arrows to put on your drawings. It is important for your thinking process to be sure that you always have one there, so that you keep orientation in mind at all times.

# Weather and Climate:

The weather of the world varies by location as relates to the distance from the equator and as influenced by aspects of geography such as the trade winds, adjacency to bodies of water, elevation, etc.


The earth's atmosphere helps to moderate the climate to prevent radical shifts in temperature from season to season and day to night.





# Koepfen's Climate Classification

The Köppen climate classification is one of the most widely used climate classification systems. It was first published by the German-Russian climatologist Wladimir Köppen (1846–1940) in **1884**, with several later modifications by Köppen, notably in 1918 and 1936. Later, the climatologist Rudolf Geiger introduced some changes to the classification system, which is thus sometimes called the Köppen–Geiger climate classification system.



Af	BWh	Csa	Cwa	Cfa	Dsa	Dwa	Dfa	ET
Am	BWk	Csb	Cwb	Cfb	Dsb	Dwb	Dfb	EF
Aw	BSh		Cwc	Cfc	Dsc	Dwc	Dfc	
	BSk				Dsd	Dwd	Dfd	

# A Timeline of Air Conditioning

**Ancient Egypt:** Ancient Egyptians are vaguely credited as being the first to use evaporative cooling by hanging wet cloth or reeds in windows and doorways. As the wind blew across the wet materials, the air in the home would be cooled.

## **Ancient Rome: Aqueducts As Air Conduits**

Wealthy citizens learn to route aqueducts through the walls of their homes. The circulating water has evaporative qualities that cool the air.

## **1758: Scientists Connect The Dots**

Benjamin Franklin and John Hadley discover the science of evaporation.

## **1851: A Pioneer In Refrigeration Emerges**

Dr. John Gorrie receives a U.S. patent for his invention that uses air blown over ice to cool hospital rooms. His idea was based on the theory that hot air in hospitals contained sickness, so cooling the air would create a healthier environment.

## **1902: The Advent Of The Commercial Air Conditioning System**

Willis Carrier invents a machine in 1902 that blows air over cold coils to control air temperature and humidity. The goal is to de-humidify the air so that paper doesn't wrinkle and ink stays fresh. Carrier founds the Carrier Air Conditioning Company of America.

## **1914: The First Residential Air Conditioner Installed**

The first in-home air conditioning unit is installed in a Minneapolis mansion. The machine is seven feet tall and twenty feet long.

## **1931: The Window Unit Invented**

H.H Schultz and J.Q Sherman invent the first window unit air conditioner. The cost of a unit (in today's money) would be up to \$600,000.


## **The 1950s: Home Air Conditioners Gain In Popularity**

Residential air conditioners catch on in suburban homes.

## **The 1970s: Central Air Becomes Standard**




# World Climate Regions



Introduced in modern times by Fitch and Branch in 1960. Reinforced by Olgay in 1963. Still the basis of current thinking, except for more subtle variations in the north.

# Climatic Regions in North America



10. Diffusion of migrating groups.

It is generally agreed that indigenous North Americans stemmed from Asia and that the waves of their migration across the Bering Strait established their populations from end to end of North and South America.


As they spread throughout North America, they entered into a broad variation of climatic environments.

These in turn impacted the type of dwellings that they created.

Dwellings also reflect nomadic vs. stable settlement.



# Climatic Regions in North America



11. Regional climate zones of the North American continent.

**Cold** -where winter is the dominant season and concerns for conserving heat predominate all other concerns. (Eg: Minneapolis, Minnesota and Ottawa, Ontario)

**Temperate** – where approximately equally severe winter and summer conditions are separated by mild transitional seasons. (i.e.: New York, NY)

**Hot-Arid** – where very high summer temperatures with great fluctuation predominate with dry conditions throughout the year. (i.e.: Phoenix, Arizona)


**Hot-Humid** – where warm stable conditions predominate with high humidity throughout the year (i.e.: Miami, Florida)

DWC




Early migration and settlement had much to do with the climate, landscape and available materials and food sources and the availability of water.






Population densities initially co-related to “good climate for life”, and have subsequently had less to do with this fact as modern systems and irrigation processes have been able to ignore these issues.



The geographic and climate regions also tend to support different cultures, ways of life, food, cooking, pace of living.

*Eating fat helps if you live in a cold climate.*






The climate regions closely align with the broad geographic regions of North America.



The availability of fresh water was also critical to these choices.




# Population Density of the United States



In the U.S. it is fairly easy to see geographic dependent patterns in settlement.

## 1990 TOTAL WATER WITHDRAWALS (excluding power)



Settlement begins to conflict with geography when water consumption begins to exceed availability. This requires more thoughtful water use...



# INDIGENOUS STRATEGIES



HOT-HUMID



TEMPERATE



HOT-ARID




COLD

FOR RETHINKING ARCHITECTURAL DESIGN

# Climate and Indigenous Housing

## TYPICAL OCCURRENCE OF INDIGENOUS ROOF TYPES











- ▲ HIGH INCLINATION ROOF
- ▲ LOW INCLINATION ROOF
- ◐ VAULTED ROOF
- FLAT ROOF



Olgay took the Fitch/Branch idea of climate and indigenous housing and analyzed roof types.

Roofs tell us a lot about housing.

- Flat roofs are to sleep on in hot climates.
- Pitched roofs shed rain.
- Low slope roofs hold snow.
- Vaulted roofs are lesser used and more style/material specific.

CLIMATE	THERMAL CHARACTERISTICS	REQUIRED ARCHITECTURAL RESPONSE	RAW MATERIALS AVAILABLE	TYPE OF TENANCY	STRUCTURAL SYSTEM EVOLVED
ARCTIC AND SUBARCTIC 	WINTER INTENSE, CONTINUOUS COLD LITTLE SOLAR LIGHT OR HEAT HIGH WINDS	LOW HEAT CAPACITY WALLS AND ROOF MINIMUM SURFACE, MAXIMUM STABILITY	SNOW	SEASONAL (HUNTING)	 SNOWDOME, ICE-AND FUR-LINED
	SUMMER MODERATE TEMPERATURES INTENSE SOLAR RADIATION	HIGH HEAT CAPACITY ROOF AND WALLS	TURF, EARTH, DRIFTWOOD	SEASONAL (HUNTING-FISHING)	 SOD-ROOFED DUGOUT
CONTINENTAL STEPPE 	WINTER INTENSE, CONTINUOUS COLD NEGLIGIBLE SOLAR HEAT HIGH WINDS	LOW HEAT CAPACITY WALLS AND ROOF MINIMUM EXPOSED SURFACE, MAXIMUM STABILITY	ANIMAL SKINS, HAIR SAPLINGS	NOMADIC (HERDING)	 PORTABLE TENSION STRUCTURE HIDE AND FELT MEMBRANES ON FRAME
	SUMMER LONG, WARM DAYS COLD NIGHTS	SHADE, VENTILATION LOW HEAT CAPACITY WALLS AND ROOF			 ROLL-UP WALL PANELS
DESERT 	LITTLE OR NO SEASONAL VARIATION HOT DAYS-COLD NIGHTS INTENSE SOLAR LIGHT AND HEAT VERY LOW HUMIDITY LITTLE RAIN	HIGH HEAT CAPACITY ROOF AND WALLS SHADE MINIMUM VENTILATION NONWATERPROOF	MUD, STONES REEDS, PALMS, SAPLINGS	PERMANENT (AGRICULTURE)	 SOLID, LOAD-BEARING MUD-MASONRY WALLS ROOFS: MUD CEMENT ON WATTLE; POLE OR PALM TRUNK RAFTERS
TROPICAL RAIN FOREST 	NO SEASONAL VARIATION HOT DAYS WARM NIGHTS INTENSE SOLAR RADIATION HIGH HUMIDITIES HEAVY RAINFALL	LOW HEAT CAPACITY WALLS AND ROOF MAXIMUM SHADE MAXIMUM VENTILATION	VINES, REEDS, BAMBOO, PALM-FRONDS, POLES	PERMANENT (AGRICULTURE, FISHING)	 SKELETAL FRAME, THATCHED ROOF, WALLS SLOPING PARASOL ROOF STILTED FLOORS



# Climate Responsive Architecture



**Indigenous structures** are valuable subjects for study because of their ingenious use of available materials and technology to produce houses which provide a remarkably high degree of thermal comfort in sometimes hostile environments.



**Vernacular architecture** has grown out of simpler forms of indigenous building as done by earlier cultures, and usually includes the same set of climate responsive parameters and similar materials but using somewhat higher technology in the construction.



**Typical “modern” 20th century architecture** has characteristically thrown out all of the lessons of both indigenous and vernacular building BUT relied on mechanical heating and cooling to moderate the interior environment with complete disregard to climate.

## Indigenous:

- Originating and living or occurring naturally in an area or environment.
- Intrinsic; innate.
- Bound to its geography.
- Using traditional, typically non-mechanized construction methods.
- Almost always pre-industrial

## Vernacular:

- Being *derived from* an indigenous building style using local materials and traditional methods of construction and ornament.

- Almost always post-industrial, using modern construction methods.

Ongoing cultural adaptation of a style (sometimes indigenous).

- *For example, Native American pueblos are indigenous and Mexican courtyard housing is vernacular.*




THERE IS A HUGE DIFFERENCE BETWEEN CLIMATE CONSCIOUS INDIGENOUS HOUSING AND “SHACKS” THAT ARE THE RESULT OF POVERTY.



...although there may remain remnants of climate effective indigenous strategies...



Poverty can result in a forced combination of old (appropriate) and new (inappropriate) materials.



## COMFORT IS THE GOAL

Comfort was possible before the invention of mechanical systems

Comfort can again be possible if we closely examine historic strategies and best practices and modify/apply them to contemporary buildings.



# Climate Responsive Architecture

“...true regional character cannot be found throughout a sentimental or imitative approach by incorporating their old emblems or the newest local fashions which disappear as fast as they appear. But if you take...the basic difference imposed on architectural design by the climatic conditions...diversity of expression can result...if the architect will use utterly contrasting indoor-outdoor relations...as focus for design conception.”

*Walter Gropius*

*What we as architects/engineers are aiming for is to take the climate motivated, environmentally sustainable/valid ideas and practices, from both indigenous and vernacular building, and to incorporate them into a current architecture that clearly responds to issues of climate (and comfort) in the design of the building.*

# Cold Climate: Indigenous Housing




Figure 3.5: Eskimo igloo, with section showing draped animal skin insulation. (Redrawn from "Primitive architecture and climate," by Fitch and Branch. Copyright © 1960 by Scientific American, Inc. All rights reserved.)



COLD

**Cold:** The severity of this climate suggests that cold temperature and wind conditions alone dictate the building sitting, form, organization and wall and window construction. Designing for all other conditions (sun, summer breezes, and humidity) are subordinated to the demands of the cold.



Also characteristic of indigenous housing is the tendency to use natural, renewable, low energy materials (*although if populations grow too quickly, materials such as wood may not be adequately replenished*). Such housing has a limited environmental impact.

COLD





This also affects the type of labour and tools that are used in construction, and typically meant inability to use “power” to assist in the building process.

**COLD**



Such housing does result in interior environments that would not be up to modern North American comfort standards. But perhaps we are aiming too high, making the gap between the environmental comfort level provided by indigenous solutions too far below our own expectations.

*That said, don't expect to wear a tank top and shorts inside in the winter.*

**COLD**




Figure 3.6: Igloo temperatures may run as much as 65°F higher than outside air temperatures using only a small oil lamp and occupant body heat. (Redrawn from "Primitive architecture and climate," by Fitch and Branch. Copyright © 1960 by Scientific American, Inc. All rights reserved.)




Figure 3.7: The summer house of the Nunamiut Eskimos follows the form of the igloo but is constructed using sticks covered with slabs of turf. (Redrawn from "Primitive architecture and climate," by Fitch and Branch. Copyright © 1960 by Scientific American, Inc. All rights reserved.)

The igloo was able to keep the sleeping bench above freezing, with limited use of a lamp and the body heat of the occupants. Most modern houses are so large that occupants are quite incapable of altering the interior temperatures.

**LESSON:** Warm air rises. People typically occupy the area close to the floor, the volume at the ceiling is warmer. Taller ceilings, more volume to heat.


COLD





The tundra -- where are  
the natural building  
materials??

**COLD**



Extreme Northern building is also affected by Permafrost. Dwellings may not allow heat to escape into the ground as thawing will destroy the permanently frozen condition of the soil and the building will “sink” rather than “float” on top of the soil.

**COLD**





These ancient Irish buildings used a similar shape to the igloo, but in this case, stone was plentiful - so these became permanent habitations.

**COLD**





- Early settlers made houses out of solid hewn logs, with mortar or mud in the cracks to keep out the wind.
- They whitewashed the interiors to reflect light better as they only had coal lamps and candles.
- Later buildings used brick and enlarged windows as glass became available.
- Taller ceilings – so hot air rises.
- No insulation as the walls were load bearing.

# Temperate: Indigenous Housing




**Temperate:** The summers are hot and humid, and the winters are cold. In much of the region the topography is generally flat, allowing cold winter winds to come in from the northwest and cool summer breezes to flow in from the southwest. The four seasons are almost equally long.

This housing maximizes **flexibility in its design** in order to be able to modify the envelope for varying climatic conditions.

TEMPERATE






The Iroquois, the Pawnee hogan, the white man's hogan, and the kolshian.

Similar techniques are seen in temperate buildings worldwide.




TEMPERATE





a

b




c

d

Figure 3.10: North American Indian tipi (a) side, and (b) front view; configured for (c) hot weather, and (d) cold weather. (After Laubin and Laubin, 1977.)



TEMPERATE



TEMPERATE

Mongolian YURT with collapsible “pantograph” side walls, and felt mat covering.





# TEMPERATE



## MAJOR LESSON FROM TEMPERATE:

- Design the envelope to allow seasonal changes
- Natural ventilation in the summer
- Close it down in the winter
- Contemporary equivalent would be operable windows and a level of solar control that changes throughout the year.



# Hot-Arid: Indigenous Housing



Figure 3.17: Acoma pueblo, New Mexico, looking northeast. (Reproduced from Knowles, 1974, by permission.)




Figure 3.18: Acoma Pueblo, New Mexico. Typical sections show the critical spacing between rows of three- and two-story houses to ensure solar access. (Redrawn from Knowles, 1974, by permission.)

**Hot-Arid:** Located in the desert region that spans California, Arizona and Nevada, the climate is characterized by extremely hot summers and moderately cold winters. The cold season lasts from November until March or April, with January temperature between 0 and 15 degrees C. A small amount of precipitation occurs during the winter. The summers are extremely hot and dry, with great temperature variations between day and night. This “*diurnal*” temperature swing is used to moderate the interior building temperatures.

**HOT-ARID**




Figure 3.19: Cutaway drawing showing construction of adobe Pueblo dwelling. (Redrawn from "Primitive architecture and climate," by Fitch and Branch. Copyright © 1960 by Scientific American, Inc. All rights reserved.)

UNINSULATED

### 3 CLIMATE AND SHELTER






Figure 3.20: Temperatures in and around an adobe dwelling. Notice that while the average inside and outside temperature are about equal, the maximum interior temperature occurs about 10 p.m. — about eight hours after the outside peak. By this time the outside temperature has actually dropped below the inside and the window can be opened for ventilative cooling. Notice that the outside temperature swing is about 40°F while the interior is only about 10°F. Finally, the shaded area shows the cooling effect of night ventilation. The thermal qualities of this primitive construction system are impressive indeed. (Redrawn from "Primitive architecture and climate," by Fitch and Branch. Copyright © 1960 by Scientific American, Inc. All rights reserved.)

Hot arid buildings use the mass of the building to moderate the heat flow through the envelope. Occupants move out to the roof to sleep if it remains too hot indoors in the night.

HOT-ARID





Historic pueblo type  
building in Chaco  
Canyon, New Mexico  
c. 1075 CE

HOT-ARID








Taos pueblos, some dating back to the 17th century and are still in use today.





**HOT-ARID**

These buildings do not employ “insulation” and have very **limited window openings** so that the sun cannot enter. They use **reflective colours** to keep what little light is let in. Small windows also exclude ventilation as they wish to exclude the hot daytime air from entering the building.







Figure 3.22: Longhouse Pueblo. Buildings were placed inside the cave in such a way that their vertical stone walls and horizontal terraces received great benefit from the low winter sun while being protected during the summer by shadow cast from the upper edge of the cave opening and by the high summer altitude of the sun. (Reproduced from Knowles, 1974, by permission.)

**HOT-ARID**

Mesa Verde used the natural landscape to take advantage of the winter and summer sun. Winter sun penetration heated up the masonry and kept the buildings warm. The cliff shaded from the summer sun, keeping things cooler.





**HOT-ARID**

Desert housing makes use of dense materials (stone/adobe) to store heat. It does get quite cold at night.





Not all hot-arid buildings are made from stone or adobe. Other accommodations are required when there is no stone, nor water with which to make mud bricks. Water is too scarce to be wasted in making a building... in this case, shade is optimized.



Bedouin tent

**HOT-ARID**

# Hot-Humid: Indigenous Housing




Figure 3.27: Simple dome hut of Banbuti Pygmies is a woven frame of twigs covered with large leaves. (Redrawn from "Primitive architecture and climate," by Fitch and Branch. Copyright © 1960 by Scientific American, Inc. All rights reserved.)





Figure 3.28: The design of this Ma'dan house (Iraq), built of 20 ft tall local reeds, has remained unchanged for 6,000 years. The sides can be raised to maximize ventilation. (After Grundfeld, 1975.)

**Hot-Humid:** is characterized by high humidity and warm summer temperatures. Day to night temperature swings during the summer are insignificant because of the extensive humidity and cloud cover which prevents surfaces from re-radiation to the night sky. Very mild winters make for a short heating season. Sunshine available all year. Often a lack of breeze.

**HOT-HUMID**



# Hot-Humid: Indigenous Housing



**FIGURE 1.2b** In hot and humid climates, natural ventilation from shaded windows is the key to thermal comfort. This Charleston, SC, house uses covered porches and balconies to shade the windows, as well as to create cool outdoor living spaces. The white color and roof monitor are also important in minimizing summer overheating.



**26.** Elegance in regional expression at the Hot-Humid island climates.

**HOT-HUMID**

# Hot-Humid: Indigenous Housing




Figure 3.26: Seminole house is an open post-and-beam construction with a gable roof of thatch. (Redrawn from "Primitive architecture and climate," by Fitch and Branch. Copyright © 1960 by Scientific American, Inc. All rights reserved.)

**HOT-HUMID**





**HOT-HUMID**





George Holton from Photo Researchers

bones and covered with animal hides—quite possibly kangaroo hides.

The Sakai of Malaysia still build some of their houses in trees. In the absence of lifts and cranes, building materials must be light enough to climb with. Flooring consists of bamboo bound with rattan. Walls are rattan, and the roof is made of attap leaves, which have a life expectancy of from four to ten years. Since the attap grows leaves up to ten feet long and four feet wide, one leaf sometimes does the entire roofing job.



Carl Frank from Photo Researchers



**HOT-HUMID**





Conical thatched grass roofs top circular dwellings built with interlaced fiber siding , Village in New Guinea

**HOT-HUMID**





Buildings are also elevated to protect their occupants from animal predators.

**HOT-HUMID**





Kandy shacks - Sri Lanka  
A combination of natural and salvaged materials.



Plentiful materials are compromised in urban areas, as shown in the construction of these “favelas” in Brazil, which use found, cheap, modern materials - sometimes what the rich throw away. Density does not permit air circulation.

**HOT-HUMID**

# CLIMATE BASED STRATEGIES



HOT-HUMID



TEMPERATE



HOT-ARID



COLD

FOR RETHINKING CONTEMPORARY  
ARCHITECTURAL DESIGN



# PASSIVE – BIO CLIMATIC DESIGN


Design must first acknowledge regional, local and microclimate impacts on the building and site.

**COLD**

**TEMPERATE**

**HOT-ARID**

**HOT-HUMID**



11. Regional climate zones of the North American continent.

Image: 1963 "Design With Climate", Victor Olgyay.

# What is Passive Design?

Start by seriously acknowledging the climate – sun, wind, light, temperature and relative humidity range


Design the building to:

- Let the sun in when it needs heat, without having to modify anything
- Prevent the sun from entering when it is unwanted and you need cooler interior temperatures
- Light the building from available daylight and avoid turning on the electric lights
- Allow natural breezes to flow through the building to cool it and bring fresh air/oxygen
- Design the walls to (in cold climates) avoid heat flow through them (by insulation)
- Design your roof to naturally shed water/snow – even include overhangs for shading

Important to locate the sun and orient the building properly



# Low Hanging Fruit



Expensive systems such as PV, micro wind turbines, various mechanical and electrical equipment

Extra insulation, better windows, thermal mass, shading devices.

Initial site and climate based design decisions that really cost nothing but will benefit the project: climate, orientation, adjacencies, massing, landscaping





If the ultimate goal is to be able to use renewable energy to reduce dependence on fossil fuels, then the load has to be light.

Imagine expecting to run a Hummer with photovoltaics?





# Climate Consultant

- In the same way that we check the Official Plan, Zoning By-laws and Building Code before commencing a design, we must also check the climate information
- A free online software that is used for validating the climate of a location
- <http://www.energy-design-tools.aud.ucla.edu/climate-consultant/request-climate-consultant.php>
- Uses EPW weather data, available from this site:
- <https://energyplus.net/weather>

# Bio-climatic Design: COLD

Where **WINTER** is the dominant season and concerns for conserving heat predominate

## RULES:

- **First INSULATE**
- *exceed* CODE requirements
- build tight to reduce air changes
- **Then INSOLATE** (let the sun shine in for free heating energy)
- roof sloped to shed rain and snow
- roof overhangs for shade during summer









YMCA Environmental Learning Centre, Paradise Lake, Ontario



TEMPERATURE RANGE


LOCATION: Harbin, Heilongjiang, CHN  
 Latitude/Longitude: 45.75° North, 126.77° East, Time Zone from Greenwich 8  
 Data Source: CSWD 509530 WMO Station Number, Elevation 142 m

LEGEND

- RECORDED HIGH - ○
- DESIGN HIGH - 
- AVERAGE HIGH - 
- MEAN - 
- AVERAGE LOW - 
- DESIGN LOW - 
- RECORDED LOW - ○
- COMFORT ZONE - 

TEMPERATURE RANGE:

- 10 to 40 °C
- Fit to Data



**MONTHLY DIURNAL AVERAGES**  
California Energy Code

**LOCATION:** HARBIN, -, CHN  
**Latitude/Longitude:** 45.72° North, 126.68° East, **Time Zone from Greenwich** 8  
**Data Source:** IVEC Data 509530 WMO Station Number, **Elevation** 469 ft

**LEGEND**

**HOURLY AVERAGES**

**TEMPERATURE: (degrees F)**

- DRY BULB MEAN
- WET BULB MEAN
- █ DRY BULB (all hours)
- █ COMFORT ZONE


**RADIATION: (Btu/sq.ft)**

- █ GLOBAL HORIZ
- █ DIRECT NORMAL
- █ DIFFUSE

Display Dry Bulb Temp  
(all hours)

**TEMPERATURE RANGE:**

- 10 to 110 °F
- Fit to Data








**COLD**





Cold climate is the most challenging in terms of preventing potential building envelope damage due to snow and moisture.



**COLD**






**COLD**

If spans are short enough, sloped roofs provide the best solution to prevent excessive snow accumulation that could cause a collapse.

Sloped roofs are also the best for shedding rainwater.







*Lodge (top and left) is multipurpose. The flat glass shop (above and right) has glazed roof slope to the north, and its detailing (below) is different from adjacent hot glass and fanbridge structures.*

Cold climate houses can take varying attitudes towards their roofs. In some cases “stops” are put on the roof to hold the snow in place (so it does not slide off) and the snow is used as extra insulation. The roof must be stronger to prevent structural collapse due to this extra weight.

**COLD**







Traditional methods of holding snow on roofs are now required by building code to prevent slides onto the public.

**COLD**






# Solar Geometry




I will talk more about the impact of solar orientation during the Façade lecture later in the term.



# Solar Access



Better solar access is possible with east-west street sections as the south face of the building will get sun for most of the day. Street spacing is adjusted so that the buildings do not block each other's south light when the angles are lowest in the winter (for good design).




North-South Section, Public Housing Estate, Giudecca Island, Venice, Italy, Gino Valle

SWL

For more complicated sections, the building height and section is adjusted to allow south light to penetrate into various exposures of the building -- in this case through courtyards and clerestory windows.



## Street Layouts



Patterns of Open Space and Buildings for Solar Access

- In cold climates the shadows and sun angles are the lowest in the winter when we really want to let the sun/heat in
- Buildings must be spaced far enough apart so that they don't shadow each other
- The sun angles are low enough though that the sun will penetrate deep into the building if the windows are properly located.






Aldo Leopold Legacy  
Center  
Baraboo, Wisconsin

The Kubala Washatko  
Architects  
LEED™ Platinum 2007





**SOLAR PV DENSITY**  
(conditioned s.f.)

**4.66** Watt / SF


**SOLAR THERMAL DENSITY**  
(conditioned s.f.)

**.012** SF / SF




- Establish solar budget:  
3,000 photovoltaic array; 50,000 kWh per year
- Set maximum building energy demand to fall within solar budget:  
8,600 Sq. Ft. building; 5.7 kWh per SF per year

A \$US250,000 PV array was included at the outset of the project budget and the building was designed to operate within the amount of electricity that this would generate.



HEATING SEASON: OCT. - APR.




HEATING SEASON MONTH: JANUARY


### Climate Narrative

Source: NOAA Weather Data Files


The climate is typical of the continental interior of North America with a large annual temperature range and with frequent short period temperature changes. The range of extreme temperatures is from about 43 to -40 degrees Celsius (110 to -40 degrees Fahrenheit). Winter temperatures (December-February) average near -7 °C (20 °F) and the summer average (June-August) is around 20 °C (in the upper 60s °F). Daily temperatures average below 0 °C (32 °F) about 120 days and above 4 °C (40 °F) for about 210 days of the year.




SWING SEASONS: MAY - JUN., SEP.




SWING MONTH: SEPTEMBER




SWING MONTH: MAY



COOLING SEASON: JUL. - AUG.



COOLING SEASON MONTH: JULY




DAILY TEMPERATURE


Heating Degree Days (HDD): 7,643  
Cooling Degree Days (CDD): 139

A complete climate analysis was conducted prior to any design work being conducted.






9:00 am



Noon




3:00 pm



Ariel Image from South

Source: \_\_\_\_\_




Site Shading Study

- June 21
- December 21

A solar analysis and ongoing solar analyses were conducted to ensure that the sun use for heating and solar avoidance were being maximized.

N



The South elevation is designed to capture energy.

The North elevation is designed for thermal resistance, daylighting and ventilation.










The buildings were arranged in a U shape around a solar meadow that ensured access to sun for passive solar heating and energy collection.





Passive Heating


- Start with bioclimatic design
- Program Thermal Zones
- All perimeter zones (no interior zones – skin load dominated building)
- Daylight all occupied zones
- Natural ventilation in all occupied zones
- Double code insulation levels
- Passive solar heating
- Shade windows during summer



Passive Cooling








Basic first tier principle of HEAT AVOIDANCE.


Passive cooling strategies use a combination of roof overhangs to shade the windows during the summer in combination with operable windows to promote natural ventilation.



Wall types and insulation levels are varied as a function of orientation and exposure


**Wall Type A**  
Interior to Exterior

- 1x Interior Wood Siding
- 2x8 Wood Studs
- Sprayed Insulation
- 1x Interior Wood Siding




**Wall Type B**  
Interior to Exterior

- 1x Interior Wood Siding
- Vapor Barrier
- 8 1/4" Structural Insulated Panel
- Air Barrier
- Air Space w/ Vertical Furring Strip
- 1x Flatboard Exterior Wood Siding




**Wall Type C**  
Interior to Exterior

- 1x Interior Wood Siding
- Vapor Barrier
- 2x8 Stud Walls with Sprayed Insulation
- 1/2" Exterior Wall Sheathing
- Air Barrier
- Air Space w/ Vertical Furring Strip
- 1x Flatboard Exterior Wood Siding



**Wall Type D**  
Interior to Exterior

- 1x Interior Wood Siding
- Vapor Barrier
- 1 1/2" Rigid Insulation
- 2x8 Stud Walls with Sprayed Insulation
- 1/2" Exterior Wall Sheathing
- Air Barrier
- Air Space w/ Vertical Furring Strip
- 1x Flatboard Exterior Wood Siding





# Bio-climatic Design: **HOT-ARID**

Where **very high summer temperatures** with great fluctuation predominate with **dry conditions** throughout the year.

## **RULES:**

- Solar avoidance : keep **DIRECT SOLAR GAIN** out of the building
- respect the **DIURNAL CYCLE**
- use heavy mass for walls
- keep windows small
- keep colours light and reflective
- roof can be flat as nothing to shed









Traditional House in Egypt


**LOCATION:** Aswan, Aswan, EGY  
**Latitude/Longitude:** 23.97° North, 32.78° East, **Time Zone from Greenwich 2**  
**Data Source:** ETMY 624140 WMO Station Number, **Elevation 194 m**

### TEMPERATURE RANGE

#### LEGEND

- RECORDED HIGH - ○
- DESIGN HIGH - 
- AVERAGE HIGH - 
- MEAN - 
- AVERAGE LOW - 
- DESIGN LOW - 
- RECORDED LOW - ○
- COMFORT ZONE - 

- TEMPERATURE RANGE:
- 10 to 40 °C
  - Fit to Data





**MONTHLY DIURNAL AVERAGES**  
California Energy Code

**LOCATION:** ASWAN, -, EGY  
**Latitude/Longitude:** 23.97° North, 32.78° East, **Time Zone from Greenwich 2**  
**Data Source:** IVEC Data 624140 WMO Station Number, **Elevation 636 ft**

**LEGEND**

**HOURLY AVERAGES**

**TEMPERATURE: (degrees F)**

- DRY BULB MEAN
- WET BULB MEAN
- █ DRY BULB (all hours)
- █ COMFORT ZONE


**RADIATION: (Btu/sq.ft)**

- █ GLOBAL HORIZ
- █ DIRECT NORMAL
- █ DIFFUSE

Display Dry Bulb Temp  
(all hours)

**TEMPERATURE RANGE:**

- 10 to 110 °F
- Fit to Data





In hot dry (arid) climates windows are kept to a minimum to prevent the sun from entering the building.

Bright stucco finishes are used to reflect light and keep the environment bright.

Sperlonga, Italy





Traditional housing responds to local culture and needs in flexible ways—often becoming more than simply shelter: house and barn, Ladakh, 10, house and shop, India, 11, house and mosque, Egypt, 12.

Using traditional forms, 13, is comparatively easy for architects catering to middle-class clients as in this Indian scheme, 14.

Contemporary self-help housing like this Algerian example, 16, tends to follow indigenous models, 15. . .



10



12



11



13



14




In some cases urban pressures have compromised valid climate based design strategies.

The “pink” town makes good use of courtyards and building shading to create a cooler place.

The stacked buildings on the left retain the small windows but expose more of themselves to the sun.

**HOT-ARID**





Vernacular architecture tends then to be building that grows out of indigenous practice and is adapted to somewhat more 20th century building.

**HOT-ARID**





## Cairo, Egypt

- Standard construction is a reinforced concrete frame
- same column size bottom to top
- Brick or tile infill
- Add floors as you have money
- See the rebar sticking out the top of the frame





- Exterior finishes applied as you can afford them
- Air conditioners added as you can afford them
- This is one of the least efficient ways to cool buildings as it is very high in energy costs and the AC units themselves produce heat as a waste by-product, making the city warmer



# Courtyard buildings:




Courtyards are used in hot arid climates and work well because sun can warm these spaces in cooler months.

*Courtyards do NOT work well in cold climates because of low winter sun angles.*

This modern building makes use of the hot-arid method that employs small windows and creates an “airy” interior by opening up courtyards and spaces on the inside of the building, that are constantly shaded.



Upper level plan



General view


**HOT-ARID**




In various climatic designs, thermal mass (stone, concrete, brick, adobe) can be used as a “thermal sink”. ie. The materials have a high capacity to hold heat and so the heat that comes to the interior of the space gets absorbed by the *building materials* and NOT the people.

People are 80% water, which also has a high thermal capacity.

Wood is an insulator so does not absorb heat.



Entrance level plan



Interior view with the dining room beyond



Modern building being marketed as a “pueblo” - “modern climate conscious adaptation”

Note light colours to reflect the light and heat.

Limited window openings to prevent excessive solar heat gain.


Use of masonry as it can work with a diurnal (hot day/cool night) cycle.

**HOT-ARID**






21



23



24



19-25, scheme by James Stirling, Michael Wilford Associates.  
 19, 20, the houses as they are today showing a shared court, 19, and a house converted into corner shop, 20.  
 21, axonometric of house when completed and as expected to be extended, 22.  
 23, a double-storey house when complete.  
 24, a single-storey extended upwards.  
 25, plan (scale: 1:150).

These more contemporary city based hot arid houses make use of courtyards to cool the house environment. The plants not only provide physical cooling, but also “mental” cooling. This becomes highly important in architectural design.

**HOT-ARID**

### Aldo van Eyck's cluster


Many of the projects were conceived in pre-cast concrete, with Western floor plans. Some schemes, such as the Danish or Polish ones, had no separation between living and dining areas. Others, like Aldo van Eyck's, had the dining room as part of the living room, but tucked to one side. Van Eyck, maintained that what the dwellers may want now could change in the future: 'The question of existing norms and forms and the ways these will change confronts the architect with an apparent choice which it should not be his concern to make'.

The Dutch scheme, sharing a courtyard with Alexander's row, is easily recognisable by its hexagonal plan. The house within the walls is a more conventional shape, roughly a square. The hexagon shape, intended to discourage additions outwards, appears to work. About 35 per cent of the residents made an exterior addition such as adding one or more rooms, yet few appeared to push out against the surrounding wall or garden space. The design helped, or some might say coerced, the resident to build up instead of out.

The surrounding wall, though, did not remain untouched. Its one-storey height was perceived to be too low, and over half the homeowners extended it, a few adding broken glass as a crown.

### Stirling's courts

Under the colonial style add-ons, the decorative roofs, diagonal trim, second-storey additions or colourful awnings can just barely be discerned the large round windows of Stirling's original design. Round windows worked in Runcorn New Town housing (1967), so why not Peru? Whether inspired by the



16

14-18, Aldo van Eyck's scheme:  
14, the houses as they are today; the hexagonal garden walls were thought to be too

low for security.  
15, a modern kitchen in van Eyck's scheme: generally the residents are of a higher income group than was planned.



17



18

16, ground floor plan (scale: 1:150)  
17, houses when completed.  
18, as they are now.

In this case the courtyards are more to the exterior of the building and also provides spatial separation and "privacy".




*A view of the residence from the southwest (below). The non-vented trombe walls are visible on the south façade. The low winter sun strikes the trombe walls full strength (opposite).*




the tradition of New Mexican architecture while adopting both a new energy strategy and the inspiration of a Mexican master in Luis Barragán. Its architects are themselves transplants. Ervin Addy arriving in Albuquerque from Texas and Robert Peters coming from Minneapolis via Chicago. The firm name, Alianza Arquitectos, symbolizes, however, the firm's intent to live and work within the Southwestern heritage and seek a vocabulary appropriate to it.

When Peters came to Albuquerque from SOM, Chicago (and work on the Sears Tower




AXONOMETRIC (NOON-WINTER)




PLAN

**HOT-ARID**






LOOKING DOWN INTO THE GUESTROOM/LIBRARY



CROSS SECTION: SOLAR STRATEGY



WALL SECTION AT TROMBE AND CLERESTORY



*The aesthetic and technical solutions of the nonvented trombe wall (both exterior and interior) are illustrated here.*

**Data**

Project: *Kress residence.*  
 Architects: *Alianza Arquitect An Architects Alliance. Ervin I Addy, partner in charge; Robert W. Peters and Jerry W. Geurts design team.*  
 Site: *1.75 acres in the foothills the Sandia Mountains. Vegetation is typical of New Mexico's high desert country.*  
 Program: *a one-bedroom residence with guest room/library to serve the retirement needs of the couple who travel extensively.*  
 Structure: *structural concrete slab on grade beams and piers with structural wood frame wall*

**HOT-ARID**








## Street Layouts

In hot arid climates where wind/ventilation is not desired, city layouts are very dense and work with overshadowing to create coolth.

Narrow shaded streets.




Aerial View of Tunis, Tunisia

Hot-Arid

SWL



Hot-Arid



Marrakech, Morocco

SWL





Kasbah, Tangier, Morocco



# Bio-climatic Design: **HOT-HUMID**

Where **warm to hot** stable conditions predominate with **high humidity** throughout the year.

## **RULES:**

- SOLAR AVOIDANCE : large roofs with overhangs that shade walls and to allow windows open at all times
- PROMOTE VENTILATION
- USE LIGHTWEIGHT MATERIALS that do not hold heat



House in Seaside, Florida

**TEMPERATURE RANGE**  
California Energy Code

**LOCATION:** Rio De Janeiro-Galeão-Jobim I, RJ, BRA  
**Latitude/Longitude:** 22.83° South, 43.25° West, **Time Zone** from Greenwich -3  
**Data Source:** TRY Brazil 837460 WMO Station Number, **Elevation** 16 ft

**LEGEND**

- RECORDED HIGH - ○
- DESIGN HIGH -
- AVERAGE HIGH -
- MEAN -
- AVERAGE LOW -
- DESIGN LOW -
- RECORDED LOW - ○
- COMFORT ZONE -

DESIGN HIGH: Residential


- 1% of Hours Above
- .5% of Hours Above
- 0% of Hours Above

DESIGN LOW: Residential

- 1% of Hours Below
- .5% of Hours Below
- 0% of Hours Below

TEMPERATURE RANGE:

- 10 to 110 °F
- Fit to Data





**MONTHLY DIURNAL AVERAGES**  
California Energy Code

**LOCATION:** Rio De Janeiro-Galeão-Jobim I, RJ, BRA  
**Latitude/Longitude:** 22.83° South, 43.25° West, **Time Zone from Greenwich** -3  
**Data Source:** TRY Brazil 837460 WMO Station Number, **Elevation** 16 ft

**LEGEND**

**HOURLY AVERAGES**

**TEMPERATURE: (degrees F)**

- DRY BULB MEAN
- WET BULB MEAN
- █ DRY BULB (all hours)
- █ COMFORT ZONE


**RADIATION: (Btu/sq.ft)**

- █ GLOBAL HORIZ
- █ DIRECT NORMAL
- █ DIFFUSE

Display Dry Bulb Temp  
(all hours)

**TEMPERATURE RANGE:**

- 10 to 110 °F
- Fit to Data





Loren A. McIntyre from Woodfin Camp & Associates

**Master Plan: Transportation, Refuse Disposal, and Food Supplies**

Few planners would care to lump these categories together, but consider the *de facto* master plan of pole-hut villages built over water. These began in the Late Stone Age and still exist in the marshes of Cambodia and New Guinea and the inner reaches of the Amazon. Transportation is by water. Garbage disposal is into water. And a good part of the food supply comes out of the water. Nor do residents have far to paddle for hunting and fishing: the refuse they throw into the water attracts marsh fowl and fish to the village.



Marc & Evelyne Bernheim from Woodfin Camp & Associates



**HOT-HUMID**



... But government-provided dwellings like these Egyptian ones, 17, are completely different from the efforts of local self-builders, 18. The result is expensive, alienating and, ultimately, self-defeating.



17



18

Traditional indigenous dwellings like this Malaysian house, 19, are built accretively. Even if results look bizarre at first, as in this Indonesian example of slum improvement, 20, the accretive approach is appropriate and effective.



19



20



23



24



25

Traditional buildings can readily accept new uses. This Malaysian house, 23, has (relatively) easily accepted a car underneath and so becomes a house-and-garage.



26



27



sultry

still

little air movement

or

very

windy

stormy

**HOT-HUMID**







What can we learn from local traditions? Bamboo is one of the fastest growing, renewable natural materials...

**HOT-HUMID**






**HOT-HUMID**



**HOT-HUMID**



# Missionary guest house, Dar-Es-Salam, Tanzania



A contemporary building that is conscious of the wind and rain and uses modern materials to replicate some effective indigenous traditions.

**HOT-HUMID**





**HOT-HUMID**



Louisiana houses of both rich and poor(er) use shutters on the windows to allow air flow while maintaining security.



Shot-gun houses

SUN-LIGHT BAPTIST CHURCH

SUN-LIGHT BAPTIST CHURCH  
Rev. James Parrish, Pastor






The traditional dog trot house is characterized by two log houses with a central connecting passageway, a porch at either side, and a chimney at each end. Developed in response to its environment, the dog trot house is successful in providing cool shaded space in the Southeast's hot, humid climate. This is accomplished primarily through its successful passive ventilation strategy.

**HOT-HUMID**





air flow diagram showing section through the central breezeway.




air flow diagram showing plan view of dog trot house.



The image above shows air above ground mainly flows above and on the east or west side of the dogtrot. A smaller volume of air travels through the breezeway but at a greater velocity.

By studying more historic vernacular types that worked well, we can re-learn the principles that made these buildings effective.


# Logan House, Tampa, FL



**HOT-HUMID**




This relatively modern building has become a model for a new kind of vernacular based upon ventilation strategies for hot-humid climates - that were derived from indigenous hot-humid buildings.



Logan House Tampa, Florida Rowe Holmes Assoc.

SWL




Logan House Tampa, Florida Rowe Holmes Assoc.

**HOT-HUMID**

# Street Layouts

In hot humid climates a very dispersed layout is desired to maximize the ability of any available breezes to cool the town and its buildings at all times.


Hot-Humid



Tocamacho Mosquito Coast Honduras

SWL





Plan of Savannah, Georgia, 1856, James Oglethorpe

Savannah uses a combination of regular streets and green spaces to help keep the city environment livable.

The plan of Savannah, Georgia uses large green spaces and squares to disperse the buildings.

Intense plantings create a cooler micro climate through shade and the action of vegetation.

Hot-Humid



SWL





Savannah, Georgia





Large homes in the southern USA adopted a strategy of large covered porches to escape the interior heat. Shaded courtyards for private interior spaces. No corridors as people went outside to move from room to room, allowing flow through ventilation in all of the rooms.

The imported European style architecture that arrived in New England was eventually modified in the south.







**HOT-HUMID**

Southern plantation houses with large shaded porches.



View from the freeway, Marina Bay, Dubai



## TEMPERATURE RANGE

### California Energy Code

**LOCATION:** ABU DHABI, -, ARE

**Latitude/Longitude:** 24.43° North, 54.65° East, **Time Zone from Greenwich 4**

**Data Source:** IWEC Data 412170 WMO Station Number, **Elevation 88 ft**

### LEGEND

- RECORDED HIGH - ○
- DESIGN HIGH -
- AVERAGE HIGH -
- MEAN -
- AVERAGE LOW -
- DESIGN LOW -
- RECORDED LOW - ○
- COMFORT ZONE -

DESIGN HIGH: Residential


- 1% of Hours Above
- .5% of Hours Above
- 0% of Hours Above

DESIGN LOW: Residential

- 1% of Hours Below
- .5% of Hours Below
- 0% of Hours Below

TEMPERATURE RANGE:

- 10 to 110 °F
- Fit to Data





**MONTHLY DIURNAL AVERAGES**  
California Energy Code

**LOCATION:** ABU DHABI, -, ARE  
**Latitude/Longitude:** 24.43° North, 54.65° East, **Time Zone from Greenwich** 4  
**Data Source:** IVEC Data 412170 WMO Station Number, **Elevation** 88 ft

**LEGEND**

**HOURLY AVERAGES**

**TEMPERATURE: (degrees F)**

- DRY BULB MEAN
- WET BULB MEAN
- █ DRY BULB (all hours)
- █ COMFORT ZONE


**RADIATION: (Btu/sq.ft)**

- █ GLOBAL HORIZ
- █ DIRECT NORMAL
- █ DIFFUSE

Display Dry Bulb Temp  
(all hours)

**TEMPERATURE RANGE:**

- 10 to 110 °F
- Fit to Data










Whether intentional, or accidental, the dense layout of the skyscrapers in Marina Bay results in shade at ground level and a much cooler street environment than a more dispersed layout would have achieved.




View from the Burj Khalifa, Dubai







The Louvre in Abu Dhabi by Jean Nouvel uses massive shading devices to protect the outdoor spaces from the sun. Natural breezes flow through. The actual museum rooms are housed in fully conditioned spaces as the artifacts demand this control.





# Bio-climatic Design: TEMPERATE

The summers are hot and humid, and the winters are cold.

**The four seasons are almost equally long.**

## **RULES:**

- BALANCE strategies between COLD and HOT-HUMID
- maximize FLEXIBILITY in order to be able to modify the envelope
- sloped roofs for rain
- overhangs for shade
- operable windows for ventilation



IslandWood Residence, Seattle



## TEMPERATURE RANGE

### California Energy Code

**LOCATION:** SEATTLE, WA, USA  
**Latitude/Longitude:** 47.45° North, 122.3° West, **Time Zone from Greenwich** -8  
**Data Source:** TMY2-24233 727930 WMO Station Number, **Elevation** 400 ft

### LEGEND

- RECORDED HIGH - ○
- DESIGN HIGH -
- AVERAGE HIGH -
- MEAN -
- AVERAGE LOW -
- DESIGN LOW -
- RECORDED LOW - ○
- COMFORT ZONE -

#### DESIGN HIGH: Residential


- 1% of Hours Above
- .5% of Hours Above
- 0% of Hours Above

#### DESIGN LOW: Residential

- 1% of Hours Below
- .5% of Hours Below
- 0% of Hours Below

#### TEMPERATURE RANGE:

- 10 to 110 °F
- Fit to Data



**MONTHLY DIURNAL AVERAGES**  
California Energy Code**LOCATION:** SEATTLE, WA, USA  
**Latitude/Longitude:** 47.45° North, 122.3° West, **Time Zone from Greenwich** -8  
**Data Source:** TMY2-24233 727930 WMO Station Number, **Elevation** 400 ft**LEGEND****HOURLY AVERAGES****TEMPERATURE: (degrees F)**


- DRY BULB MEAN
- WET BULB MEAN
- █ DRY BULB (all hours)
- █ COMFORT ZONE

**RADIATION: (Btu/sq.ft)**

- █ GLOBAL HORIZ
- █ DIRECT NORMAL
- █ DIFFUSE

 Display Dry Bulb Temp  
(all hours)**TEMPERATURE RANGE:**

- 10 to 110 °F
- Fit to Data



Back

Next






IslandWood is an education center, on Bainbridge Island near Seattle, Washington. It was awarded LEED™ Gold Certification in 2002.

Mithun Architects

KEEN Engineering (Stantec)





<http://www.designshare.com/index.php/projects/islandwood/images>





- Exploration of passive heating systems
- Solar orientation, creation of “solar meadow” to ensure solar gain
- Large overhangs to prevent overheating
- Natural ventilation
- Solar hot water heating
- Photovoltaic panels







Porch zones that are covered to allow use during rain events which are pretty common in Seattle.







- Rainwater collection from all roofs – use water for irrigation
- Composting toilets
- Waterless urinals and low flush toilets
- Living Machine to treat blackwater to tertiary level of purification







Extensive use of natural materials like wood

Spaces use natural lighting where possible to cut down on use of electricity